

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

AUG 14 1961

CONSERVATION DIVISION  
Wichita, Kansas

8-14-61

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

15-163-02983-00-00

File No. \_\_\_\_\_ County: \_\_\_\_\_ Rooks

Location: SE NE SE \_\_\_\_\_ Sec. 5 Twp. 8 Rge. \_\_\_\_\_ (E) (W) 17

Name of Field: \_\_\_\_\_ Total Depth: 3388

I have this date completed supervision of plugging of:

Lease Name: Bohert \_\_\_\_\_ Well No. 2

Operator's Full Name: Okmar Oil Co

Complete Address: 820 Union Natl Bk Wichita, Kansas

Plugging Contractor: Glenn & Smith Pipe Pulling

Address: Ellinwood, Kansas License No. \_\_\_\_\_

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 5PM Day 9 Month 8 Year 61

The above well was plugged as follows:

8 5/8" 108' circulated with cement - 5 1/2" 3385' with 100 sax cement, perf  
3095' - set 5 sax cement on bottom with dump bailer, sand and plugs re  
3080' set 4 sax cement with dump bailer - pulled 1000' 5 1/2" to 500'  
circulated hole with heavy mud through 5 1/2" at 500', displaced 20  
sax cement through 5 1/2" at 500', heavy mud to 170', ~~sax~~ displaced 20  
sax cement through 5 1/2" at 170', heavy mud to 35' and cemented to 0'.  
Mudding and cementing by Sun Cementing Co.

Signed: [Signature]  
Conservation Division Agent

Reviewed: [Signature]  
Field Supervisor

Remarks:

INVOICED  
DATE 8/17/61  
INV. NO. 3540-W