

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-02984-00-00

RECEIVED  
STATE CORPORATION COMMISSION

NOV 30 1964  
11-30-64  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Okmar Oil Co

Complete Address: 1132 Wichita Plaza Wichita, Kansas

Lease Name Eckert Well No. 4

Location NE SE SE Sec. 5 Twp. 8 Rge. (E) (W) 17

County Rooks Total Depth 3358

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Southwest Casing Pulling

Address: Great Bend, Kans License No. 399

Operation Completed: Hour 5PM Day 23 Month 11 Year 64

The Above well was plugged as follows:

8 5/8" 108' circulated with cement - 5 1/2" 3353' with 75 sax cement - PB to 3315' - Perf 3091. 5 1/2" squeezed in Dakota section with cement.

Sanded back to 3070', set 4 sax cement with dump bailer.

Pulled 390' 5 1/2" to 300', circulated hole with heavy gel mud through 5 1/2"

at 300', displaced 25 sax cement through 5 1/2" at 300', heavy mud to 180'

displaced 25 sax cement through 5 1/2" at 180', heavy mud to 35', set 10

sax cement to bottom cellar.

Mudding and cementing by Southwest Company pump truck.

I hereby certify that the above well was plugged as herein stated.

DATE 12/1/64

INV. NO. 241-11

Signed: [Signature]  
Well Plugging Supervisor

INVOICED