

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

15-163-02985-00-00

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SW SW NE

SEC. 5 TWP. 8 RGE. 17

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease _____ Emery _____

Operator V. D. Sidey Address Russell, Kans

Field _____ County Rooks

Total Depth 3327 Feet.

Plugging Contractor Barnes & Sons Pipe Pulling

Plugging Contractor's License No. 9

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 122' circulated with cement - 5 1/2" at 3314' with 100
sax cement behind - Lane Wells plugs to 3270' - perforated at
3105'.

Filled with sand to 3100', set plug and 4 sax cement with dump bailer,
Pulled 2725' 5 1/2" - pumped hole full mud (30 sax HalcoGel & 10 sax
Baroid) - pumped cementing plug to 180', followed by 60 sax
cement - Cement 180' to 0'.

Mudding and cementing by Halliburton Co - 500# max pump pressure.

Edon Perry
District Conservation Agent

Date 11-11-54

11-15-54

PLUGGING
FILE SEC. 518 R. 17
BOOK PAGE 22 LINE 28