

15-163-03199-00-00

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENTS REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUL 16 1963  
7-16-63  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Okmar Oil Co

Complete Address: 1130 Wichita Plaza Wichita, Kansas

Lease Name Robert Well No. 5

Location SE SE SE Sec. 5 Twp. 8 Rge. (E) (W) 17

County Rooks Total Depth 3390

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Southwest Casing Pulling

Address: Great Bend, Kans License No. 399

Operation Completed: Hour 3PM Day 13 Month 7 Year 63

The Above well was plugged as follows:

~~8 5/8" 103' circulated with cement - 5 1/2" 3387' with 100 sax cement - sand back to 3370', set 4 sax cement with dump bailer - 5 1/2" parted 32 jts down - run back in hole to fish - failed to do any good - pulled 5 3/8" to 550', circulated hole with heavy gel mud, displaced 20 sax cement through 5 1/2" at 550', heavy mud to 260', displaced 20 sax cement through 5 3/8" at 26-', heavy mud to 35', set bridge and filled to bottom cellar with cement.~~

Mudding and cementing by Southwest Company pump.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edon Lee  
Well Plugging Supervisor

DATE 7-16-63

INV. NO. 7417-W