

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 163-21,052 (of this well) 00-00

Operator's Full Name GEORGE P. CRAWFORD.

Complete Address Route #1 BOX 93 - NATOMA, KANS. 67651

Lease Name COOPER Well No. #1

Location NE-SW-SW Sec. 8 Twp. 8 Rge. 17 (E) (W)

County ROCKS Total Depth 1216 FT

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated LOST HOLE

Plugging Contractor PIONEER DRILLING CO. INC.

Address 308 WEST MILL PLAINVILLE, MS. License No. _____

Operation Completed: Hour 4:00 PM Day 10th Month JUNE Year 1980

The above well was plugged as follows:

8 5/8" 1316^{FT} SP. DID NOT CIRCULATE COMPLETELY - SP. PARTED @ 390^{FT}
HAD PUMPED IN TO CNT. SP. 300^{FT} HALLIBURTON LIGHT AND
100^{FT} COMMON 2% GEL-3% CA-CL. → HAD SOLID BRIDGE AT. 390^{FT}
7 7/8" BIT WENT OUT OF HOLE AT 390^{FT} TO 730^{FT} → THEY REMOVED
TOP 390^{FT} OF SP. TRIED TO REPLACE IT BUT COULDN'T REPLACE IT.
ORDERED 325^{FT} 50% POZ MIX 6% GEL + 10^{FT} HULL'S (SPOTTED WITH DRILL STEM)
1ST PLUG. @ 682^{FT} W/ 125^{FT} CNT. → 2ND PLUG. - 3 HULL'S + 140^{FT} CNT @ 310^{FT}
3RD PLUG. 7 HULL'S + 75^{FT} CNT IN TOP AND 10^{FT} IN RAT HOLE

I hereby certify that the above well was plugged as herein stated (BY HALLIBURTON CNT.)

INVOICED
DATE 6-13-80
INV. NO. 2361W

RECEIVED
JUN 13 1980
JUN 13, 1980
CONSERVATION DIVISION
Wichita, Kansas

Signed: [Signature]
Well Plugging Supervisor