

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

APR 9 1964  
APR 9, 1964  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Okmar Oil Co  
Complete Address: 1130 Wichita Plaza Wichita, Kans  
Lease Name Hrabe Well No. 1 SWD  
Location NE NW SW Sec. 8 Twp. 8 Rge. (E) (W) 17  
County Rooks Total Depth 3702  
Abandoned Oil Well      Gas Well      Input Well      SWD Well X D & A       
Other well as hereafter indicated:       
Plugging Contractor: Sun Cementing Co  
Address:      License No.       
Operation Completed: Hour 3PM Day 6 Month 4 Year 64

The Above well, was plugged as follows:

13" 41' - 8 5/8" 1300' circulated with cement - 5 1/2" 3319' 100 sax behind -  
5 1/2" squeezed twice in Dakota section 200 sax cement - cement circulated  
to top - 4 1/2" liner cemented in 3248' to 3395'  
Pumped hole full heavy mud ( 40 sax Gel) pumped wiper plug followed by  
70 sax cement at 500# standing pump pressure - cement to 0' - no pipe  
recovery.

Mudding and cementing by Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

Signed: *Edwin Leary*  
Well Plugging Supervisor

INVOICED

DATE 4/9/64  
INV. NO. 8922-11