

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-163-20915-00-00

RECEIVED
STATE CORPORATION COMMISSION
MAR 11 1974
CONSERVATION DIVISION
Wichita, Kansas
3-11-74

Operator's Full Name Clinton Oil Company

Complete Address Box 1201 Wichita, Kansas

Lease Name W. H. Brown Well No. 1-V

Location SW SE SW Sec. 6 Twp. 8 Rge. (E) (W) 17

County Rooks Total Depth 3420'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Red Tiger Drlg.

Address License No.

Operation Completed: Hour 1:15 P Day 7 Month 3 Year 1974

The above well was plugged as follows:

RTD 3420' 8 5/8 csg set at 239' cwc 150 sk. Cmt. Mat. reg. poz.
at 600'

Gunned pits, circulated heavy mud, set cementing plug and displaced 70 sk cmt thru

drill pipe. Heavy mud to 215' set cementing plug and displaced 20 sk cmt thru drill

pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo P. Massey
Well Plugging Supervisor

DATE 3/12/74

INV. NO. 8712-U