

DISTRICT CONSERVATION AGENT'S REPORT

15-163-00910-00-00

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 110-17  
LOCATION SW SW NE  
SEC. 7 TWP. 8 RGE. 17

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Hrabxe  
Operator Murfin Drg Co Address 910 Union Natl Bldg Wichita  
Field \_\_\_\_\_ County Rooks  
Total Depth 3433 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 165' circulated with cement - 5 1/2" at 3433' with  
20 sax cement behind.

Filled with chat to 3400' set 4 sax cement with dump bailer,  
pulled 2300' 5 1/2", filled with mud to 157', set rock and 20 sax cement  
mud to 35', set rock and 10 sax cement to bottom cellar.

**PLUGGING**  
FILE SEC 7 T 8 R 17W  
BOOK PAGE 110 LINE 17

*E. J. [Signature]*  
District Conservation Agent  
Date 6-24-53

6-29-53