

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUL 20 1959

CONSERVATION DIVISION  
Wichita, Kansas

7-20-59

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

15-163-03058-00-00

File No. 49-35 County: Rooks

Location: SE NE NE Sec. 7 Twp. 8 Rge. 17 (E) (W)

Name of Field: \_\_\_\_\_ Total Depth: 3372

I have this date completed supervision of plugging of:

Lease Name: Hrabe Well No. 2

Operator's Full Name: C & G Drg Co

Complete Address: 107 Rule Bldg Wichita, Kans

Plugging Contractor: Forbes Casing Pulling Co

Address: Great Bend, Kans License No. 49

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 6PM Day 6 Month 7 Year 59

The above well was plugged as follows:

8 5/8" / 169' circulated with cement - 5 1/2" 3369' with 100 sax cement.

Filled with sand to 3350', set 4 sax cement with dump bailer, pulled  
2690' 5 1/2" - pumped hole full heavy mud ( 40 sax Gel), pumped cementing  
plug followed by 125 sax cement.

Mudding and cementing by Globe Cementing Co. Pump pressure 550# to 300#.

Signed: *Edon Lett*  
Conservation Division Agent

Reviewed: *J. Lewis Brock*  
Field Supervisor

Remarks:

PLUGGING  
FILE SEC. 7 T 8 R 17W  
BOOK PAGE 49 LINE 35