

KANSAS

 STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

AUG 10 1967

8-10-67

CONSERVATION DIVISION  
Wichita, Kansas

15-163-20048-00-00

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name C - G Drilling Company

Complete Address: 107 Rule Building Wichita, Kansas

Lease Name Hrabe "A" Well No. 2

Location NE SW SW Sec. 7 Twp. 8 Rge. 17 (E) (W) X

County Rooks Total Depth 3406

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Co. Tools

Address:      License No.     

Operation Completed: Hour 4:30 A Day 8 Month 8 Year 1967

The Above well was plugged as follows:

RTD 3406' 8 5/8 csg set at 202' cwc 140 sc.  
Gunned pits, circulated heavy mud, set cementing plug at 1040' and displaced 100 sc cem.  
thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sc cement thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base  
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/10/67

INV. NO. 6110-d

Signed:   
Well Plugging Supervisor