

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUL 31 1974

CONSERVATION DIVISION  
Wichita, Kansas

7-31-74

15-163-20448-0000

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Clinton Oil Co.

Complete Address Box 1201, Wichita, Kansas 67201

Lease Name Margaret Smith Well No. 1

Location NW SE NW Sec. 7 Twp. 8 Rge. (E) (W) 17

County Rooks Total Depth 3446'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Kelso Pipe Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 11:30 A Day 29 Month 7 Year 1974

The above well was plugged as follows:

Total Depth 3446' 20 3/4 csg set at 200' cwc 135 sk.

5 1/2 csg set at 3393' cw 175 sx.

5 1/2 csg PBTD 3350' with top perf. (3132'.)

Set 5 1/2 wood plug at 3000' -poured 20' sand -dumped 4 sk cmt W/dump bailer. (3000-2950)

Cutoff and recovered 2585' of 5 1/2 csg.

Pumped down 10 3/4 csg with 25 sk gel & water W/300 lbs hulls -70 sk cmt -10 sk

gel & water -released 10 3/4 plug and pumped 70 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Lea J. Massey  
Well Plugging Supervisor

INVOICED

DATE 7/31/74

INV. NO. 9633-W