

*12*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION NE SW NW

SEC. 8 TWP. 8 RGE. 17

Dry Hole x Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 3 Lease Turner "B" 617 W. Center

Operator Murfin Dpg Co Address Wichita, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3343 Feet.

Plugging Contractor same

Plugging Contractor's License No. \_\_\_\_\_

Address \_\_\_\_\_

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 161' circulated with cement.

Gunned pits, circulated hole with heavy mud, set cementing plug at  
550', displaced 20 sax cement through drill pipe, heavy mud to  
100', set cementing plug and displaced 20 sax cement through drill  
pipe, heavy mud to 40', set cementing plug, 1/2 sack hull's and 10  
sax cement to bottom cellar.

*E. J. Perry*  
District Conservation Agent

Date 9-19-57

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 23 1957  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 8 T. 8 R. NW  
BOOK PAGE 47 LINE 34