

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 065-00442-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 11/6/54.

Well Operator: VESS OIL CORPORATION KCC License #: 5030

Address: 8100 E. 22nd Street North, Bldg. 300 City: Wichita

State: KS Zip Code: 67226 Contact Phone: (316) 682 - 1537 X103

Lease: Hoof Well #: #101 Sec. 9 Twp. 10S S. R. 23W East West

NE - NE - SW Spot Location / QQQQ County: Graham

2310' Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

2310' Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8-5/8' Set at: 217' Cemented with: 150 Sacks

Production Casing Size: 5-1/2" Set at: 3955' Cemented with: 200 Sacks

List (ALL) Perforations and Bridgeplug Sets: Toronto - 3691-95'; LKC - 3704-3885'

Elevation: 2433 (G.L. / K.B.) T.D.: 3955' P.BTD: 3942' Anhydrite Depth: 1972'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): In accordance with KCC rules and regulations

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Joel Stull

Phone: (785) 483 - 9169

Address: P.O. Box 307 City / State: Natoma, KS 67651

Plugging Contractor: Allied Cementing Co., Inc. KCC License #: 99996

Address: P.O. Box 31, Russell, KS 67665-0031 Phone: (785) 483 - 2627

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 3/10/06 Authorized Operator / Agent: [Signature]

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

* WELL PLUGGED 3-13-06. DAW

DRILLER'S LOG

Imperial Drilling Company, Inc.
903 Union National Bank Building
Wichita 2, Kansas

15065 60442-00-00

Hoof "A" No. 1
NE NE SW Sec. 9-10S-23W
Graham County, Kansas

Total Depth: 3955'

Elevation: 2433' R.B.

Commenced: 11-6-54 Completed: 11-18-54

Production: 3000 B.O.P.D.

Contractor: Imperial Drilling Company, Inc.
Wichita, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 217' W/150 sacks cement.
Set 5 1/2" Casing at 3955' W/200 sacks cement.

Figures indicate bottom of formations:

Sand and Shell	217'		
Surface Clay, shale and shells	895'		
Shell, Shells and Sand	1410'		<u>TOPS</u>
Shale and Shells	1475'		
Dakota Sand	1700'	Anhydrite	1972' (/ 461)
Shale and Shells	1995'	Heebner	3669' (-1236)
Anhydrite	2040'	Toronto	3690' (-1257)
Shale and Shells	2350'	Lansing	3702' (-1269)
Shell and Shells	2515'	Rotary Total Depth	3955' (-1522)
Shale and Shells	2680'		
Shale and Lime	3593'		
Lime	3955'		
Total Depth	3955'		

RECEIVED

MAR 13 2005

KCC WICHITA

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

IMPERIAL DRILLING COMPANY, INC.

By: Ray L. Bacon
Vice-President

Subscribed and sworn to before me this 27th day of December, 1954.

My commission expires:

November 9, 1957

Marilyn E. Fox
Notary Public