

RECEIVED

APR 10 2006

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING APPLICATION

KCC WICHITA

Form CP-1  
September 2003

This Form must be Typed  
This Form must be Signed  
All blanks must be Filled

145-20713-00-00

Please TYPE Form and File ONE Copy

API # 15-145-~~20713~~-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 9-7-1980

Well Operator: Fred J Nuss KCC License #: 31273  
(Owner / Company Name) (Operator's)

Address: 158 East State Road 4 City: Hoisington

State: Kansas Zip Code: 6/544 Contact Phone: (620) 653 2594

Lease: Weathers Well #: \_\_\_\_\_ Sec. 1 Twp. 21 S. R. 15  East  West

C SE - NE - SE Spot Location / QQQQ County: Pawnee

1980 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

330 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8 5/8 Set at: 874 Cemented with: 425 SX Sacks

Production Casing Size: 5 1/2 Set at: 3684 Cemented with: 300 Sacks

List (ALL) Perforations and Bridgeplug Sets: 3670-74 3620-31 2754-58 2618-24 2562-68  
plug 2498 2382-88 1830-40

Elevation: 1936 ( G.L. /  K.B.) T.D.: 3698 PBDT: 3685 Anhydrite Depth: 885  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): As per K.C.C. requirements and instructions

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? \_\_\_\_\_

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Fred J Nuss

Phone: (620) 653 2594

Address: 158 E State Rd City / State: Hoisington Ks 67544

Plugging Contractor: Ketso Mike's Testing & Salvage, Inc. KCC License #: 31529  
(Company Name) (Contractor's)

Address: P.O. BOX 467 Chase Ks Phone: (620) 938 2943

Proposed Date and Hour of Plugging (if known?): 60 days mid June they are backed up

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 4/7/2006 Authorized Operator / Agent: Fred J Nuss  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

WHEATLAND OIL & GAS INC  
510 PETROLEUM BLDG

REPLACEMENT CARD: #2  
#1 WEATHERS

1-21-15W  
C E/2 NE SE

WICHITA, KS 67202

CONTR RAMCO DRILLING CO

CTY PAWNEE

GEOL DAVID P WILLIAMS

FIELD FREY NW


ELV 1936 KB SPD 9/7/80

CARD ISSUED 7/2/81

IP D&A/ARB

1931 GL

API 15-145-20,713



RECEIVED  
APR 10 2006  
KCC WICHITA

LOG	Tops	Depth: Datum
ARH		885 ± 1081
KRI		1831 - 105
WINF		1885 - 51
TOP		2890 - 954
HEEB		3237 - 1301
IATAN		3339 - 1403
LANS		3349 - 1413
BKC		3584 - 1648
VIOLA		3614 - 1678
ARB		3670 - 1734
LTD		3685 - 1749
RTD		3698 - 1762

8 5-8 874/425SX, 5 1 2 " 3684-300SX

DST (1) 3614-3645 (VIOLA) 30-30-30-30. REC 90' GCM. SIP 821-433#. FP 83-69 87-69#. HP 2064-1962#. BHT 120'

DST (2) 3647-3682 (ARB) : 30-30-30-30. REC 15' HOCM. SIP 572-447#. FP 72-72 . 104-83#. HP 1978-1926#. BHT 121'

MIC - CO. PF (ARB) 3670-74 (EST), SWB DWN & TSTD NON-COMMERCIAL. PF (VIOLA) 3620-31 (EST), SWB DWN & TSTD NON-COMMERCIAL, P&A

INFO RELEASED: 10/28/82, WAS TEMP ABD

#2

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS



CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    Robert E. Krehbiel, Commissioner    Michael C. Moffet, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Nuss, Fred J.  
158 E State Rd 4  
Hoisington, KS 67544

April 11, 2006

Re: WEATHERS #1  
API 15-145-20713-00-00  
E2NESE 1-21S-15W, 1980 FSL 330 FEL  
PAWNEE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely

David P. Williams  
Production Supervisor

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888