

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-5-117

RECEIVED

APR 14 2006

KCC PKT 4-14-06  
Per CP-1

15-051-03178-00-00  
Drilled 1955

KCC WICHITA

WELL NAME Brock

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Coax. Div.  
office within 30 days.

WELL NUMBER 6

1650 Ftt. from S Section Line

4290 Ftt. from E Section Line

SEC. 12 TWP. 15 RGE. 18 (●) or (○)

COUNTY Ellis

Date Well Completed 1956

Plugging Commenced 3-30-06

Plugging Completed 3-30-06

LEASE OPERATOR Charter Energy, Inc.

ADDRESS P O Box 252, Great Bend, KS 67530

PHONE (620) 793-9090 OPERATORS LICENSE NO. 9090

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on March 29, 2006 (date)

by Herb Deines (KCC District Agent's Name).

Is AC-1 filled? Unknown If not, is well log attached? None in file

Producing Formation LKC/Arbuckle Depth to Top Arb 3585 Bottom 3590 T.D. 3648

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				10 3/4"	350	None
				7"	3643	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set  
Hook on to 7" x 10 3/4" annulus. Pressure to 1000#. Run Tubing to 2000'. Pump 110 sx Swift Multi Density w/300# hulls. Pull tubing to 1600'. Pump 150 sx w/300# hulls. Pull to 700'. Mix 60 sx and circ cement. Pull tubing top off hole. Pressure to 200#. Standing @ 50#.

Name of Plugging Contractor Swift Services License No. 32382 N/A

Address P O Box 466, Ness City, KS 67560

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Charter Energy, Inc.

STATE OF Kansas COUNTY OF Barton, s.s.

Steve Baize (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) PO Box 252, Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 12th day of April, 2006, 1906

Donna Moore  
Notary Public

My Commission Expires: 2-17-2009



PCT