

RECEIVED

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

APR 06 2006

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Ritchie Exploration, Inc. Address: P.O. Box 783188 Wichita, KS 67278-3188 Phone: (316) 691-9500 Operator License #: 4767 Type of Well: D & A Docket #: The plugging proposal was approved on: 3/19/06 by: Eric Maclaren Is ACO-1 filed? No If not, is well log attached? No Producing Formation(s): List All (If needed attach another sheet) Depth to Top: Bottom: T.D.

API Number: 15 - 171-20610-0000 Lease Name: Rodenberg Well Number: #1 Spot Location (QQQQ): SE - NW - NW - 1043 Feet from North / South Section Line 1146 Feet from East / West Section Line Sec. 25 Twp. 17 S. R. 31 East West County: Scott Date Well Completed: 3/19/06 Plugging Commenced: 3/19/06 Plugging Completed: 3/19/06

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: Surface, 0, 238, 8-5/8, 7 jts., 0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


1st Plug set at 2350' with 50 sacks of 60/40 poz, 6% gel, 2% cc; 2nd plug set at 1500' with 80 sacks; 3rd plug set at 600' with 50 sacks; 4th plug set at 270' with 50 sacks; 5th plug set at 60' with 20 sacks; 15 sacks in the rat hole and 10 sacks in mouse hole. Total 275 sacks. by: Allied Cementing, Plug Down 9:30 a.m. 3/19/06.

Name of Plugging Contractor: Val Energy, Inc. License #: 5822 Address: P.O. Box 116 Wichita, KS 67201-0116

Name of Party Responsible for Plugging Fees: Ritchie Exploration, Inc. State of Kansas County, Sedgwick, ss.

Craig Caulk (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Handwritten Signature] (Address) P.O. Box 783188 Wichita, KS 67278-3188



SUBSCRIBED and SWORN TO before me this 5th day of April, 2006 My Commission Expires: 5/4/07 Notary Public

Handwritten initials 'AM'