

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-20309-00-00
Spot: NWSESE Sec/Twnshp/Rge: 30-21S-17W
984 feet from S Section Line, 1006 feet from E Section Line
Lease Name: BOYD Well #: 1
County: PAWNEE Total Vertical Depth: 2210 feet

Operator License No.: 32302
Op Name: KEY GAS CORP.
Address: 155 N. MARKET - SUITE 900
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1955		WITH 2 SX CMT
PROD	4.5	2209	0	WITH 125 SX CMT
SURF	8.625	788		

\$71.83

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/05/2006 2:30 PM
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.
Proposal Rcvd. from: MIKE MCNAUL Company: KEY GAS CORPORATION Phone: (316) 662-6977

Proposed Plugging Method: SET CIBP @ 1955' & 2 SX CMT. PRESSURE TEST CASING TO 300#. PERFORATE @ 810'. PUMP CMT DONW 4 1/2" & CIRCULATE TO SURFACE UP 8 5/8" X 4 1/2" ANNULUS WITH 300 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/05/2006 3:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 1955' & 2 SX CMT. PRESSURE TEST CASING TO 300#. PERFORATE @ 810'. PUMP CMT DOWN 4 1/2" AND CIRCULATE TO SURFACE UP 8 5/8" X 4 1/2" ANNULUS WITH 300 SX CMT. CIRCULATED 25 SX CMT TO PIT.

Perfs:


Top	Bot	Thru	Comments
2058	2086		
2006	2038		

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND ACID & CEMENT.

Plugged through: CSG

INVOICED
4-13-06
2006061477

District: 01



Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
APR 13 2006
KCC WICHITA

Form CP 2/3

pet