

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-01155-00-00
Spot: SWSENW Sec/Twnshp/Rge: 25-30S-8W
2970 feet from S Section Line, 3630 feet from E Section Line
Lease Name: WEST SPIVEY UNIT Well #: 5
County: KINGMAN Total Vertical Depth: 4450 feet

Operator License No.: 32446
Op Name: MERIT ENERGY COMPANY
Address: 13727 NOEL RD., STE 500
DALLAS, TX 75240

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4424		200 SX CMT
SURF	8.625	183		250 SX CMT

\$ 144.63

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/08/2006 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE Company: QUALITY WELL SERVICE, INC. Phone: (620) 257-2719

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 03/08/2006 5:00 PM KCC Agent: DAVE WERTZ

Actual Plugging Report:

Sanded back to 4190' and capped with 5 sack of cement. Shot 5-1/2" off at 1540'. Pulled tubing to 1257' and spotted 35 sacks of cement. Pulled tubing to 750' and spotted 35 sacks of cement. Pulled tubing to 250' and circulated cement to surface.

60/40 posmix with 4% gel

Allied #16307

Perfs:

Top	Bot	Thru	Comments
4388	4394		
4350	4360		
4322	4328		

RECEIVED
KCC DISTRICT #2
APR 10 2006
WICHITA, KS

INVOICED

4-14-06

DATE: _____
2006061479

Remarks:

Plugged through: TBG

District: 02

Signed

David Wertz
(TECHNICIAN)

~~INVOICED~~ per

RECEIVED
APR 14 2006
KCC WICHITA

per