

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22324-00-00
Spot: E2E2NE Sec/Twnshp/Rge: 12-15S-23W
1470 feet from N Section Line, 120 feet from E Section Line
Lease Name: APPLEGATE UNIT Well #: 1
County: TREGO Total Vertical Depth: 4244 feet

Operator License No.: 5252
Op Name: NIXON, R P OPERATIONS, INC
Address: 207 W 12TH
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	219		

137.93
A

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/06/2006 12:00 PM
Plug Co. License No.: 5184 Plug Co. Name: SHIELDS OIL PRODUCERS INC
Proposal Rcvd. from: BURT BEERY Company: R.P. NIXON OPERATIONS, INC. Phone: (785) 628-3834

Proposed Plugging Method: Order 225 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.
No ar buckle plug.

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE
Date/Time Plugging Completed: 04/06/2006 8:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

1st. Plug at 1675' w/25 sxs.
2nd. Plug at 750' w/100 sxs.
3rd. Plug at 275' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed _____

Case Morris

(TECHNICIAN)

INVOICED

DATE 4-11-06
INVOICE NO. 2006061467

RECEIVED

APR 11 2006

KCC WICHITA

Form CP-2/3

APR 07 2006

pet