

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-07625-00-01
Spot: SENWNW Sec/Twnshp/Rge: 32-15S-13W
990 feet from N Section Line, 990 feet from W Section Line
Lease Name: BOOMHOWER A Well #: 1
County: RUSSELL Total Vertical Depth: 3600 feet

Operator License No.: 32325

Op Name: POPP OPERATING, INC.

Address: 191 NE 150 RD. PO BOX 187
HOISINGTON, KS 67544

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	12.5	480	0	w/365 sxs cmt

\$ 117.00

Well Type: OH DH KCC PRT UIC Docket No: 4-11-06 Date/Time to Plug: 03/15/2006 2:00 PM

Plug Co. License No.: 6426 per a district #4 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC

Proposal Rcvd. from: RICKY POPP

Company: POPP OPERATING, INC.

Phone: (620) 653-2737

Proposed Plugging Method:

This well was never used as a disposal. Was an OWWO.

Plugging Proposal Received By: CASE MORRIS

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 03/15/2006 5:45 PM

KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Originally plugged in 1950 - pulled 550' of 8 5/8".
When they ran back in with 8 5/8" - could not get over the old 8 5/8" and may have smashed it.
Pulled 8 5/8" back out. Could not get past 670' with tubing.
Pulled tubing to 665' and pumped 60 bbls heavy drilling mud, followed with 80 sxs 60/40
pozmix - 10% gel cement.
Pulled to 60' and circulated with 60 sxs cement.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Case Morris

(TECHNICIAN)

INVOICED

DATE 4-11-06
INV. NO. 2006061468

RECEIVED

APR 11 2006

KCC WICHITA

Mar 27 2006

PRT