

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22341-00-00
Spot: E2NESE Sec/Twnshp/Rge: 31-13S-21W
2000 feet from S Section Line, 330 feet from E Section Line
Lease Name: LEONARD Well #: 1-31
County: TREGO Total Vertical Depth: 4172 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 372
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	222		

\$ 135.59

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/07/2006 3:55 PM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: DOWNING-NELSON OIL CO., INC. Phone: (785) 628-3449

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: EDWIN SCHUMACHER Witness Type: NONE
Date/Time Plugging Completed: 04/08/2006 6:20 AM KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

1st. Plug at 1730' w/25 sxs.
2nd. Plug at 915' w/100 sxs.
3rd. Plug at 275' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

INVOICED
DATE 4-13-06
REF. NO. 2006061476

District: 04

Signed Ed Schumacher
(TECHNICIAN)

RECEIVED
APR 13 2006
KCC WICHITA

APR 11 2006

pet