

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23515-00-00
Spot: SESWSW Sec/Twnshp/Rge: 17-10S-17W
400 feet from S Section Line, 790 feet from W Section Line
Lease Name: VIVIAN GANOUNG Well #: 1
County: ROOKS Total Vertical Depth: 3740 feet

Operator License No.: 32639
Op Name: CORAL PRODUCTION CORPORATION
Address: 1600 STOUT STREET, SUITE 1500
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	237		170 SX CMT.

\$121.55

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/08/2006 7:00 PM
Plug Co. License No.: 9431 Plug Co. Name: VONFELDT DRILLING, INC
Proposal Rcvd. from: JIM WEBER Company: CORAL PRODUCTION CORPORATI Phone: (303) 623-3573

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: JAY PFEIFER WitnessType: NONE
Date/Time Plugging Completed: 03/08/2006 10:35 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perfs:

1st. Plug at 3700' w/25 sxs.
2nd. Plug at 1430' w/25 sxs.
3rd. Plug at 900' w/100 sxs.
4th. Plug at 275' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

INVOICED
DATE 4-17-06
INV. NO. 2006061483


RECEIVED
APR 17 2006
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

APR 12 2006

PCT