

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-10891-00-00
Spot: SWNENW Sec/Twnshp/Rge: 3-22S-13W
990 feet from N Section Line, 3630 feet from E Section Line
Lease Name: GATES A Well #: 3
County: STAFFORD Total Vertical Depth: 3800 feet

Operator License No.: 5893
Op Name: PRATT WELL SERVICE, INC.
Address: PO BOX 847
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3798	0	WITH 150 SX CMT
SURF	8.625	254		WITH 175 SX CMT

123,50
\$1

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/03/2006 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND TO 3450' & 5 SX CMT. PERFORATE @ 760'. PUMP 75 SX CMT DOWN TUBING. CIRCULATE CMT UP 5 1/2". CHECK BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/03/2006 1:45 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3450' & 5 SX CMT WITH BAILER. PERFORATED 5 1/2" AT 760'. RAN TUBING TO 775'. PUMPED 75 SX CMT DOWN TUBING, CIRCULATING CMT TO SURFACE UP 5 1/2" CASING. NO BLOW ON 8 5/8" X 5 1/2" ANNULUS. PULLED TUBING. SQUEEZED 50 SX CMT DOWN 5 1/2" CASING. MAXIMUM PRESSURE 800 PSIG. SHUT IN PRESSURE = 550 PSIG. PRESSURED 8 5/8" X 5 1/2" ANNULUS TO 2000# + PSIG. NO CMT ENTRY.

Perfs:


Top	Bot	Thru	Comments
3738	3748		

RECEIVED
APR 17 2006
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: CSG

District: 01



Signed Richard W. Lacey
(TECHNICIAN)

INVOICED
DATE 4-17-06
INV. NO. 2006061494

Form 2/03

PWS