

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-20364-00-01
Spot: W2SE Sec/Twnshp/Rge: 30-21S-17W
1320 feet from S Section Line, 1980 feet from E Section Line
Lease Name: BOYD Well #: 1A-30
County: PAWNEE Total Vertical Depth: 2320 feet

Operator License No.: 32302
Op Name: KEY GAS CORP.
Address: 155 N. MARKET - SUITE 900
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1950		WITH 2 SX CMT
PROD	4.5	2109	0	WITH 150 SX CMT
SURF		837		

\$ 75.40

Well Type: SWD UIC Docket No: D18435.0 Date/Time to Plug: 04/04/2006 1:00 PM
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.
Proposal Rcvd. from: MIKE MCNAUL Company: KEY GAS CORP. Phone: (316) 662-6977

Proposed Plugging Method: SET CIBP @ 1950' WITH 2 SX CMT. PEFORATE AT 860'. PUMP 300 SX CMT DOWN 4 1/2" CASING & CIRCULATE CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/04/2006 5:45 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

ANHYDRITE =1108'. SET CIBP @ 1950' WITH 2 SX CMT. PERFORATED AT 860'. PUMP 300 SX CMT DOWN 4 1/2" CIRCULATING CMT TO SURFACE UP 8 5/8" X 4 1/2" ANNULUS. SHUT IN 8 5/8" X 4 1/2" ANNULUS & PRESSURED TO 300 PSIG WITH 2 SX CMT. SHUT IN PRESSURE 250 PSIG.

Perfs:


Top	Bot	Thru	Comments
2010	2097		

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND ACID.

Plugged through: CSG

RECEIVED
APR 17 2006
KCC WICHITA

District: 01



Signed Richard W. Lacey
(TECHNICIAN)

INVOICED
DATE 4-17-06
WV. NO. 2006061488

Form CSG

PKT