

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-085-20061-00-00
Spot: SWNW Sec/Twnshp/Rge: 29-6S-16E
3497 feet from S Section Line, 4558 feet from E Section Line
Lease Name: JENKINS Well #: 12-29
County: JACKSON Total Vertical Depth: 2224 feet

Operator License No.: 33233
Op Name: HEARTLAND OIL & GAS, INC.
Address: 1610 INDUSTRIAL PARK DRIVE
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2209		404 SX CMT
SURF	8.625	218		140 SX CMT

\$ 72.28

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/02/2006 8:00 AM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: GEL FROM 2166' TO 2089', CMT FROM 2089' TO 1498', GEL FROM 1498' TO 250', CMT FROM 250' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/02/2006 5:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Tagged bottom at 2125'. Pulled tubing to 2119' and pumped 75 sacks of gel and 70 sacks of cement with 1 sack of cotton seed hulls. Had cement from 2119' to 1507' and gel from 1507' to 250'. Pumped 30 sacks of cement from 251' to surface.

Perfs:

Top	Bot	Thru	Comments
2035	2039		
2027	2029		
2008	2010		
1984	1986		
1969	1974		
1953	1955		
1946	1950		
1851	1853		
1548	1550		

RECEIVED
KCC DISTRICT #3

APR 11 2005 TCH

CHANUTE, KS

RECEIVED
APR 17 2006
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed

Taylor C. Herman

(TECHNICIAN)

INVOICED
DATE 4-17-06
INV. NO. 2006061491