

15-179-20171-00-00

Form CP-3
Rev. 6-26-62

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 7 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Murfin Drilling Company and J. S. Kantor,

Complete Address: 617 Union Center Building, Wichita, Kansas.

Lease Name Schwarzenberger Well No. 1

Location App. -SE-SE-NE, Sec. 31 Twp. 7 Rge. (E) (W) 26

County Sheridan Total Depth 4034'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Paine Drilling Company, Incorporated,

Address: Box "D", Hill City, Kansas. License No.

Operation Completed: Hour 12:30 PM Day 4 Month 1 Year 1969

The Above well was plugged as follows:

220'--7" OD Surface casing, cement circulated with 125 Sx.
Top of Dakota section @ 1125'.

Circulated hole with heavy mud. Pulled DP to 1150' and displaced 65 Sx. cement thru
DP from 1150' to 825'. Pulled DP to 245' and displaced 15 Sx. cement thru DP from
245' to 185'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 5 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED
DATE 1/7/69
INV. NO. 9158-W