

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JAN 5, 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Phoenix Drilling Corporation,

Complete Address Suite, 400 North Woodlawn, Wichita, Kansas.

Lease Name Sumner Well No. 1

Location CSW-NW Sec. 28 Twp. 7 Rge. (E) (W) 27

County Sheridan Total Depth 4135'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 5:00 PM Day 31 Month 12 Year 1969

The above well was plugged as follows:

218'--8 5/8" Surface casing, cement circulated,
Top of Dakota section @ 1250'.

Circulated hole with heavy mud. Pulled DP to 1470' and displaced 100 Sx. cement thru
DP from 1470' to 1145'. Pulled DP to 240' and displaced 25 Sx. cement thru DP from
240' to 165'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. D. Nichols
Well Plugging Supervisor

INVOICED
DATE 1-5-70
INV. NO. 1187-W