


DISTRICT CONSERVATION AGENT'S REPORT



TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 99-42  
LOCATION SW SW NE  
SEC. 2 TWP. 7 RGE. 27

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Sniffen

Operator Anschutz Drg Co Address 709 Union Natl Wichita,

Field \_\_\_\_\_ County Sheridan

Total Depth 4080 Feet.

Plugging Contractor E & L Casing Pulling

Plugging Contractor's License No. 249

Address \_\_\_\_\_

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 165' circulated with cement - 5 1/2" at 3910' with 100  
sax cement behind - Lane Wells plugs to 3849', perforated 3840'.  
Sand to 3830', set 4 sax cement with dump bailer, pulled 2400'  
5 1/2" @ heavy mud to 350', set rock bridge and 30 sax cement, mud  
to 35', set bridge and 10 sax cement to bottom cellar.

District Conservation Agent

Date 9-28-56

**PLUGGING**  
FILE SEC 2 T 7 R 27w  
BOOK PAGE 99 LINE 42

RECEIVED  
COMMISSION  
OCT 1, 1956  
DIVISION