

KANSAS

14

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name John O. Farmer, Incorporated,

Complete Address: 370 West Wichita, Russell, Kansas.

Lease Name Leidig Well No. 1

Location SW-SW-NW Sec. 1 Twp. 7 Rge. (E) (W) 27

County Sheridan Total Depth 4085'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 7:00AM Day 18 Month 7 Year 1967

The Above well was plugged as follows:

286'--8 5/8" surface pipe, cement circulated with 150 Sx.
Dakota section from 1695' to 1875'.

Ran DP. to 1895' and displaced 100 Sx. cement thru DP. Pulled DP. to
300' and displaced 20 Sx. cement thru DP. Pulled DP., set plug @ 40'
with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION
JUL 21, 1967
JUL 21 1967

I hereby certify that the above well was plugged as herein stated.

INVOICED

CONSERVATION DIVISION
Wichita, Kansas

Signed: *N. L. T. Jechels*
Well Plugging Supervisor

DATE 7/21/67
INV. NO. 6010-w