

KANSAS

AL

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 24 1972
CONSERVATION DIVISION
Wichita, Kansas
JAN 24 1972

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Abercrombie Drilling, Incorporated,

Complete Address 801 Union Center Building, Wichita, Kansas.

Lease Name Sniffin Well No. 1

Location CNE-SW-NW Sec. 2 Twp. 7 Rge. (E) (W) 27

County Sheridan Total Depth 4082'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 1:00 PM Day 22 Month 1 Year 1972

The above well was plugged as follows:

249'--8 5/8" Surface casing, cement circulated with 175 Sx. (6 3/4" Hole).
Top of Dakota section @ 1225'.

Circulated hole with heavy mud. Pulled DP to 1450' and displaced 50 Cu. Ft. cement
thru DP from 1450' to 1125'. Pulled DP to 280' and displaced 25 Cu. Ft. cement thru
DP from 280' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Nichols*
Well Plugging Supervisor

INVOICED
DATE 1-28-72
INV. NO. 5060-W