



KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JUN 6 1968 JUN 6, 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Leo J. Dreiling Oil Company,

Complete Address: Victoria, Kansas.

Lease Name Flanagin Well No. 1

Location SW-SW Sec. 12 Twp. 7 Rge. (E) (W) 32

County Thomas Total Depth 4278

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: L. J. Dreiling & Sons, Incorporated,

Address: Victoria, Kansas. License No. _____

Operation Completed: Hour 2:00PM Day 2 Month 6 Year 1968

The Above well was plugged as follows:

260'--8 5/8" Surface Pipe, cement circulated with 200 Sx.
Top of Dakota section @ 1460'.

Circulated hole with heavy mud. Pulled DP to 1685' and displaced 100 Sx. cement thru
DP from 1685' to 1360'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from
275' to 215'. Pulled DP, set bridge @ 140' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: A. L. Diebold
Well Plugging Supervisor

INVOICED
DATE 6/6/68
INV. NO. 17896-4