

*4*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
APR 1 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
APR 1, 1968

Operator's Full Name John O. Farmer, Incorporated,

Complete Address: 370 West Wichita, Russell, Kansas.

Lease Name Keller Well No. 1

Location NE-NE-NE Sec. 29 Twp. 7 Rge. (E) (W) 28

County Sheridan Total Depth 4190

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Above

Address:      License No.     

Operation Completed: Hour 1:30 PM Day 30 Month 3 Year 1968

The Above well was plugged as follows:

245'--8 5/8" Surface pipe, cement circulated with 150 Sx.  
Top of Dakota Section @ 1325'.

Circulated hole with heavy mud. Pulled DP to 1550' and displaced 100 Sx. cement thru  
DP from 1550' to 1225'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from 275'  
to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of  
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. L. Deibel*  
Well Plugging Supervisor

DATE 4/1/68  
INV. NO. 7501-W