

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 110-26
LOCATION SE NE SE
SEC. 35 TWP. 7 RGE. 26

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Scheetz
Operator G-M-R Oil Address Box 1033 Wichita, Kans
Field _____ County Sheridan
Total Depth 4102 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 200' circulated with cement - 5 1/2" at 3908' with
100 sax cement behind - perforated at 3720' - Baker plugs to
3756' - filled with chat to 3700', set 4 sax cement with dump
bailer, pulled 3180' 5 1/2" - filled with mud to 200', set rock
and 10 sax cement, mud to 35', set rock and 10 sax cement to
bottom cellar.

PLUGGING
FILE SEC 35 T 7 R 26
BOOK PAGE 110 LINE 26

JUL 6 1953

Edw. Pett
District Conservation Agent
Date 6-29-53