

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
APR 19 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
APR 19 1968

Operator's Full Name John O. Farmer, Incorporated.

Complete Address: 370 West Wichita, Russell, Kansas.

Lease Name Newland Well No. 1

Location NW-NW-SW Sec. 30 Twp. 7 Rge. (E) (W) 27

County Sheridan Total Depth 4160

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Above

Address:      License No.     

Operation Completed: Hour 12:30 AM Day 11 Month 4 Year 1968

The Above well was plugged as follows:

252'--8 5/8" Surface pipe, cement circulated.  
Top of Dakota section @ 1300'.

Circulated hole with heavy mud. Pulled DP to 1525' and displaced 100 Sx. cement thru  
DP ffrom 1525' to 1200'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from  
275' to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/19/68  
INV. NO. 7615-W

Signed: A. B. Nichols  
Well Plugging Supervisor