



KANSAS

Form CP-3  
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 26 1968 NOV 26/19 68  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Rains & Williamson Oil Company,

Complete Address: 1425 Wichita Plaza Building, Wichita, Kansas.

Lease Name City of Hoxie Well No. 1

Location SW-SE Sec. 32 Twp. 7 Rge. (E) (W)27

County Sheridan Total Depth 4163

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Above

Address:      License No.     

Operation Completed: Hour 7:30 AM Day 21 Month 11 Year 1968

The Above well was plugged as follows:

283'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 1300'.

Circulated hole with heavy mud. Pulled DP to 1525' and displaced 100 Sx. cement thru  
DP from 1525' to 1200'. Pulled DP to 300' and displaced 20 Sx. cement thru DP from  
300' to 240', Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Dichel  
Well Plugging Supervisor

INVOICED  
DATE 11/26/68  
INV. NO. 8892-W