

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-22339-00-01  
Spot: NENWSW Sec/Twnshp/Rge: 18-14S-19W  
2310 feet from S Section Line, 4380 feet from E Section Line  
Lease Name: BARNES Well #: 1  
County: ELLIS Total Vertical Depth: 3820 feet

Operator License No.: 30961

Op Name: A P S, INC.

Address: 750 MOUNT PLEASANT RD  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3817	0	w/unknown sxs cmt
SURF	8.625	249	0	w/unknown sxs cmt

\$ 124.15

Well Type: SWD

UIC Docket No: D20686.0

Date/Time to Plug: 04/13/2006 9:00 AM

Plug Co. License No.: 99996

Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: WILLARD BARNES

Company: APS, INC.

Phone: (785) 625-5361

Proposed Plugging Method: DV tool at 1491' w/350 sxs. Holes in casing.

Plugging Proposal Received By: BRUCE BASYE

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 04/13/2006 11:40 AM

KCC Agent: BRUCE BASYE

Actual Plugging Report:

Tied onto 8 5/8" x 5 1/2" annulus and pumped zero water - 500# pressure.  
Tied onto 5 1/2" casing and pumped 175 sxs 60/40 pozmix - 10% gel with 500# hulls.  
Max. P.S.I. 500#. S.I.P. 0#.

Perfs:

**INVOICED**

DATE 4-19-06

TR. NO. 2006061498

**RECEIVED**  
**APR 19 2006**  
**KCC WICHITA**

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Bruce D. Basye  
(TECHNICIAN)

Form CP-2/3

APR 17 2006

PST

THUNDERBIRD DRILLING, INC.

18-14-19W

BOX 18407

#1 BARNES 330' FNI & 900' FW SW/4

WICHITA, KS 67218

CONTR CO TOOLS

CTY ELLIS

GEOL

FIELD PLEASANT SE

2197 KB CM 3/26/81 <sup>CARD</sup>ISSUED 5/7/81 IP P 25 BO & 25 BWPD

+	+	+
.	.	.
+	+	+

API 15-051-22,339

ARB OH 3817-20

SMP	TOPS	DEPTH	DATUM
ANH		1462	+ 735
B ANH		1508	+ 689
HEEB		3453	-1256
LANS		3500	-1303
ARB		3815	-1618
RTD		3820	-1623
NO LOG			

8 5/8" 249/175sx; 5 1/2" 3817/100

DST (1) 3512-35 (ARB)/30-45-30-45, 30' OIL SPKD M, SIP 256-91#, FP 54-64#

DST (2) 3652-90 (LKC)/30-30-30-30, 10' M, SIP 64-64#, FP 64-64#

DST (3) 3696-3753 (LKC)/30-45-45-60, 50' GIP, REC 70' OCM (27% OIL), SIP 1045-945#, FP 73-100#

DST (4) 3779-3814 (LKC, PENN)/30-45-30-45, 15' M, SIP 401-183#, FP 64-64#

DST (5) 3789-3820 (LKC, PENN)/30-45-45-60, 150' HO CM, 180' MDY FROGGY OIL SIP 1165-1174#, FP 91-201#

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

MICT - CO, (ARB OH), ONFU 1600' (1400' OIL), POP