

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-23202-00-04  
Spot: SENWSENE Sec/Twnshp/Rge: 28-33S-8E  
3351 feet from S Section Line, 941 feet from E Section Line  
Lease Name: KENNEDY Well #: 3-28  
County: COWLEY Total Vertical Depth: 2369 feet

Operator License No.: 32557  
Op Name: BLUESTEM, INC  
Address: 1226 W COUNTY LINE RD  
CEDAR VALE, KS 67024

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2369		125 SX
SURF	8.625	450		330 SX

\$1 76.99

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/30/2006 10:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: JOHN ELMORE Company: ELMORE'S, INC. Phone: (620) 249-2519

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/31/2006 3:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

3/30/2006 -- RIH with 1" tubing at 2226'. Pumped 10 bbls gel flush and 10 sacks of common cement with 3% gel. Tagged at 2000'.  
3/31/2006 -- Shot 4-1/2" casing at 1200'. POOH with 28 joints of casing. RIH with 1" tubing at 500'. Mixed and pumped 150 sacks of 60/40 posmix with 4% gel to surface.  
Cement ticket #6444

Perfs:

Top	Bot	Thru	Comments
2272	2290		

RECEIVED  
KCC DISTRICT #2  
APR 10 2006  
WICHITA, KS

RECEIVED  
APR 19 2006

Remarks:

Plugged through: TBG

District: 02

Signed

Duane Krueger  
(TECHNICIAN)

INVOICED

DATE

4-19-06

WEL. NO.

2006061502

Form CP-2/3

*m*

*PT*