

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-23232-00-00
Spot: NESWSENE Sec/Twnshp/Rge: 28-33S-8E
3078 feet from S Section Line, 970 feet from E Section Line
Lease Name: KENNEDY Well #: 4-28
County: COWLEY Total Vertical Depth: 2379 feet

Operator License No.: 32557
Op Name: BLUESTEM, INC
Address: 1226 W COUNTY LINE RD
CEDAR VALE, KS 67024

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2379		125 SX CMT
SURF	8.625	446		160 SX MCT

\$ 77.32

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/28/2006 10:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: JOHN ELMORE Company: ELMORE'S, INC. Phone: (620) 249-2519

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/29/2006 1:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

3/28/2006 -- RIH with tubing at 2225'. Pumped 10 bbls gel flush and 10 sacks of common cement with 3% gel. Tagged cement at 2136'. Shot 4-1/2" casing at 900'.
3/29/2006 -- POOH with 21 joints of 4-1/2" casing. RIH with 1" at 500'. Mixed and pumped 145 sacks of 60/40 posmix with 4% gel to surface.
Cement ticket #6443

Perfs:

Top	Bot	Thru	Comments
2290	2304		

RECEIVED
KCC DISTRICT #2
APR 10 2006
WICHITA, KS

RECEIVED
APR 19 2006
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 4-19-06
2006061502

Handwritten mark

Handwritten mark