

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23511-00-00
Spot: SESWSWSE Sec/Twnshp/Rge: 31-9S-18W
250 feet from S Section Line, 2025 feet from E Section Line
Lease Name: CHURCH Well #: 1
County: ROOKS Total Vertical Depth: 3760 feet

Operator License No.: 32639
Op Name: CORAL PRODUCTION CORPORATION
Address: 1600 STOUT STREET, SUITE 1500
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	238		

\$1 122.20

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/27/2006 12:00 PM
Plug Co. License No.: 9431 Plug Co. Name: VONFELDT DRILLING, INC
Proposal Rcvd. from: DOUG VONFELDT Company: CORAL PRODUCTION CORPORATI Phone: (303) 623-3573

Proposed Plugging Method: Order 225 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE BASYE WitnessType: NONE
Date/Time Plugging Completed: 03/27/2006 4:30 PM KCC Agent: BRUCE BASYE

Actual Plugging Report:

Perfs:

1st. Plug at 3745' w/25 sxs.
2nd. Plug at 1620' w/25 sxs.
3rd. Plug at 970' w/100 sxs.
4th. Plug at 290' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

RECEIVED
APR 19 2006
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Bruce Basye

(TECHNICIAN)

INVOICED

DATE 4-19-06

REF. NO. 2006061504

Form CP-2/3

APR 17 2006

PT