

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-20093-00-00
Spot: NWSWNW Sec/Twnshp/Rge: 4-27S-9W
3689 feet from S Section Line, 5016 feet from E Section Line
Lease Name: LAWSON Well #: 1
County: KINGMAN Total Vertical Depth: 4211 feet

Operator License No.: 5427
Op Name: LAUCK, D.R. OIL CO., INC.
Address: 221 S. BROADWAY, STE 400
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4206		75 SX CMT
SURF	8.625	254		225 SX CMT

136.86

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/07/2006 8:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: MELVIN URBAN Company: D. R. LAUCK OIL CO., INC. Phone: (620) 564-2013

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: GREG EVES Witness Type: PARTIAL
Date/Time Plugging Completed: 03/07/2006 5:00 PM KCC Agent: DONALD HOBERECHT

Actual Plugging Report:

Sanded back 50' above perforations with 5 sacks of cement on top of sand. Shot casing at 1500'. Pulled to 1350' and spotted 35 sacks of cement. Pulled casing to 900' and spotted 35 sacks of cement. Pulled casing to 300' and circulated cement to surface with 80 sacks of cement.

60/40 posmix with 4% gel
Copeland Acid & Cement

Perfs:

Top	Bot	Thru	Comments
4206	4211		
3054	3948		

RECEIVED
KCC DISTRICT #2
APR - 6 2006
WICHITA, KS

RECEIVED
APR 19 2006
KCC WICHITA

Remarks:

Plugged through: CSG

District: 02

Signed

(TECHNICIAN)

INVOICED

4-19-06

DATE 2006061505

Form CP-2/3

PJT