

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-20118-00-00
Spot: NWNESE Sec/Twnshp/Rge: 5-27S-9W
2361 feet from S Section Line, 1093 feet from E Section Line
Lease Name: BRADSHAW Well #: 1
County: KINGMAN Total Vertical Depth: 4553 feet

Operator License No.: 5427
Op Name: LAUCK, D.R. OIL CO., INC.
Address: 221 S. BROADWAY, STE 400
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	4440		
SURF	10.75	237		

147.97

Well Type: SWD UIC Docket No: D14696.0 Date/Time to Plug: 03/08/2006 8:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: MELVIN URBAN Company: D. R. LAUCK OIL CO., INC. Phone: (620) 524-2013

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: WitnessType: PARTIAL
Date/Time Plugging Completed: 03/08/2006 5:00 PM KCC Agent: DONALD HOBERECHT

Actual Plugging Report:

Sanded back 50' above perforations. Open hole with 6 sacks of cement on top of sand. Shot casing at 1750'. Pulled to 1400' and spotted 50 sacks of cement. Pulled to 900' and spotted 50 sacks of cement. Pulled to 300' and circulated 150 sacks of cement to surface.

60/40 posmix with 4% gel

Copeland Acid & Cement

Perfs:

RECEIVED
KCC DISTRICT #2
APR 17 2006
WICHITA, KS


RECEIVED
APR 19 2006
KCC WICHITA

Remarks:

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

INVOICED

4-19-06

Form CP-2/3

DATE

2006061505

