

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21551-00-00
Spot: SENENWNW Sec/Twnshp/Rge: 4-33S-8W
420 feet from N Section Line, 1060 feet from W Section Line
Lease Name: LONE TREE FARMS Well #: 1
County: HARPER Total Vertical Depth: 4537 feet

Operator License No.: 6236
Op Name: M.T.M. PETROLEUM
Address: PO BOX 82
SPIVEY, KS 67142

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	213		175 SX CMT.

Handwritten: 41 147.45

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/24/2006 4:00 PM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: JOE LIVINGSTON Company: DUKE DRILLING CO., INC. Phone: (620) 793-0835

Proposed Plugging Method: Pump 35 sxs @ 1250'; 35 sxs @ 800'; 35 sxs @ 270'; 25 sxs @ 60' to surf; 15 sxs in rathole and 10 sxs in mousehole.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE
Date/Time Plugging Completed: 03/24/2006 7:00 PM KCC Agent: GREG EVES

RECEIVED
APR 19 2006
KCC WICHITA
RECEIVED
KCC DISTRICT #2
APR 14 2006
WICHITA, KS

Actual Plugging Report:
Pulled drill pipe up to 1250' and pumped 35 sacks of cement. Pulled drill pipe to 800' and pumped 35 sacks of cement. Pulled drill pipe to 270' and pumped 35 sacks of cement. Pulled drill pipe to 60' and circulated 25 sacks of cement to surface. Pumped 15 sacks of cement in rathole and 10 sacks of cement in mousehole.
155 sacks of 60/40 posmix with 4% gel
Allied #16743

Perfs:

Remarks:
Plugged through: DP

District: 02

Signed Greg Eves
(TECHNICIAN)

INVOICED
4-19-06
2006061506

Form CP-2/3

Handwritten: a

Handwritten: PLOT