

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-19210-00-01

Spot: SENW

Sec/Twnshp/Rge: 1-20S-1W

3688 feet from S Section Line, 3405 feet from E Section Line

Lease Name: BITIKOFER

Well #: 2

County: MCPHERSON

Total Vertical Depth: 2926 feet

Operator License No.: 5399

Op Name: AMERICAN ENERGIES CORPORATION

Address: 155 N. MARKET, STE 710
WICHITA, KS 67202

String Size Depth (ft) Pulled (ft) Comment

PROD 5.5 3108 125 SX CMT

SURF 8.625 219 NOT AVAILABLE

95.10

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 02/08/2006 11:00 AM

Plug Co. License No.: 5399

Plug Co. Name: AMERICAN ENERGIES CORPORATION

Proposal Rcvd. from: DOUG WARD

Company: AMERICAN ENERGIES CORPORAT Phone: (620) 628-4424

Proposed Plugging Method: Place 50' of sand over perms. Fill hole with mud and set 35 sxs @ 440'. Pull tubing to 270' and circ slurry mix from 270' to surf.

Plugging Proposal Received By: MICHAEL WILSON

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 02/08/2006 5:00 PM

KCC Agent: GREG EVES

Actual Plugging Report:

Sanded to 2810' and capped with 5 sacks of cement. Ran tubing to 450' and pumped 2 yds slurry mix. Pulled tubing to 270' and pumped 10 yds slurry mix and circulated to surface.

McPherson Concrete Products #51783 & #51784
Total -- 12 yds slurry mix (22 sxs per yd, 10% sand)

Perfs:

Top	Bot	Thru	Comments
2914	2922		
RECEIVED KCC DISTRICT #2 FEB 14 2006 WICHITA, KS INVOICED DATE 4-19-06 REF. NO. 2006061499 RECEIVED APR 19 2006 KCC WICHITA			

Remarks:

Plugged through: TBG

District: 02

Signed

Greg Eves

(TECHNICIAN)

A

PCT