

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-20496-00-00
Spot: SENWNWSE Sec/Twnshp/Rge: 35-19S-1W
2006 feet from S Section Line, 2077 feet from E Section Line
Lease Name: RATZLAFF Well #: 1
County: MCPHERSON Total Vertical Depth: 2950 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N. MARKET, STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2948		125 SX CMT
SURF	8.625	224		

SH 95.88

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/03/2006 10:30 AM
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION
Proposal Rcvd. from: DOUG WARD Company: AMERICAN ENERGIES CORPORAT Phone: (620) 628-4424

Proposed Plugging Method:

Sand 50' above perms and cap w/ 4 sxs cmt; pump 35 sxs cmt @ 450'; pull tbg 250' & circ to surf.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 03/03/2006 12:30 PM KCC Agent: GREG EVES

Actual Plugging Report:

Sanded to 2850' and capped with 4 sacks of cement. Ran tubing to 450' and pumped 2 yds of slurry mix. Pulled tubing to 270' and pumped 7 yds of slurry mix and circulated to surface.
McPherson Concrete Products #52092
Total 9 yds slurry mix -- Slurry mix = 22 sxs/yd w/ 10% sand

Perfs:

Top	Bot	Thru	Comments
2911	2918		

RECEIVED
KCC DISTRICT #2
MAR 27 2006
WICHITA, KS
INVOICED
DATE 4-19-06
TIME, SERIAL 2006061499
RECEIVED
APR 19 2006
KCC WICHITA

Remarks:

Plugged through: DP

District: 02

Signed Greg Eves
(TECHNICIAN)

M

PT