

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-20514-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 36-19S-1W
2310 feet from S Section Line, 2429 feet from E Section Line
Lease Name: MATHES HARTMAN Well #: 1
County: MCPHERSON Total Vertical Depth: 2950 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N. MARKET, STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2943		125 SX CMT
SURF	8.625	212		150 SX CMT

\$ 95.88

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/08/2006 1:00 PM
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION
Proposal Rcvd. from: DOUG WARD Company: AMERICAN ENERGIES CORPORAT Phone: (620) 628-4424

Proposed Plugging Method: Sand 50' above perms & cap with 4 sxs cmt; cut off csg & pull to 540' & pump 35 sxs cmt; pull csg to 265' & circ cmt to surf.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 03/08/2006 3:20 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 2800' and capped with 4 sacks of cement. Cut off casing at 2025' and pulled out of hole. Ran tubing to 540' and pumped 35 sacks of cement. Pulled tubing to 265' and circulated cement to surface.

60/40 posmix with 4% gel

McPherson slurry mix #52148 & #52149

Perfs:

Top	Bot	Thru	Comments
2924	2927		

INVOICE
DATE 4-19-06
TEL NO. 2006061499
RECEIVED
KCC DISTRICT #2
MAR 21 2006
WICHITA, KS
RECEIVED
APR 19 2006

Remarks:

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

M

POT