

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-113-20529-00-00  
Spot: E2E2NE Sec/Twnshp/Rge: 22-19S-1W  
3954 feet from S Section Line, 372 feet from E Section Line  
Lease Name: WILLIAM LOVETT Well #: 1  
County: MCPHERSON Total Vertical Depth: 2960 feet

Operator License No.: 5399  
Op Name: AMERICAN ENERGIES CORPORATION  
Address: 155 N. MARKET, STE 710  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2948	668	35 SX CMT
SURF	8.625	146		100 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/28/2006 8:00 AM  
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION  
Proposal Rcvd. from: DOUG WARD Company: AMERICAN ENERGIES CORPORAT Phone: (620) 628-4424

Proposed Plugging Method: Sand to 50' above perms (2910' - 2944') and cap w/ 4 sxs cmt; pump cmt from 450' to surf.

Plugging Proposal Received By: MICHAEL WILSON WitnessType: PARTIAL  
Date/Time Plugging Completed: 03/01/2006 3:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

Sanded perforations to 2810' and capped with 4 sacks of cement. Pulled casing and ran tubing to 450'. Circulated slurry mix from 450' to surface.  
Approx. 560' of 4-1/2" casing pulled.  
McPherson Concrete Products #52032 & #52038  
13 yds slurry mix total  
Slurry mix = 22 sxs cmt/yd w/ 10% sand

Perfs:

Top	Bot	Thru	Comments
2910	2944		

RECEIVED  
KCC DISTRICT #2  
MAR 27 2006  
WICHITA, KS

RECEIVED  
APR 19 2006  
KCC WICHITA

Remarks:  
Plugged through: TBG

District: 02

Signed Greg Eves  
(TECHNICIAN)

**INVOICED**  
DATE 4-19-06  
INV. NO. 2006061499

PKT