

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-079-20579-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 4-22S-2W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease Name: SCHRAG Well #: 1
County: HARVEY Total Vertical Depth: 3180 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N. MARKET, STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3178		75 SX CMT
SURF	8.625	208		150 SX CMT

\$ 103.35

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/09/2006 10:00 AM
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION
Proposal Rcvd. from: DOUG WARD Company: AMERICAN ENERGIES CORPORAT Phone: (620) 654-7149

Proposed Plugging Method: Sand to 50' above perms & cap w/ 4 sxs cmt; pull pipe to 450' & pump 35 sxs; pull pipe to 250' & circ to surf.

Plugging Proposal Received By: MICHAEL WILSON WitnessType: PARTIAL
Date/Time Plugging Completed: 03/09/2006 3:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

Sanded perforations to 2865' and capped with 4 sacks of cement. Production casing was parted at 288'. Tubing was ran to 330' which was as far as possible. Cement was circulated from 330' to surface.

9 yds slurry mix = 198 sxs cement

McPherson Concrete Products #52165

9 yds slurry mix = 22 sxs/yd w/ 10% sand

Perfs:

Top	Bot	Thru	Comments
2914	2922		

**RECEIVED
KCC DISTRICT #2
MAR 21 2006
WICHITA, KS**

**RECEIVED
APR 19 2006
KCC WICHITA**

Remarks:

Plugged through: TBG

District: 02

Signed Greg Eves
(TECHNICIAN)

INVOICED

DATE 4-19-06

NO. 2006061499

PET