

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21331-00-00
Spot: NWSWSESE Sec/Twnshp/Rge: 23-27S-6W
460 feet from S Section Line, 1290 feet from E Section Line
Lease Name: WATERLOO Well #: 1
County: KINGMAN Total Vertical Depth: 4192 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4193	3125	
SURF	8.625	288		

\$1 136.24

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/22/2006 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: DICK SCHREMMER Company: BEAR PETROLEUM, INC. Phone: (316) 524-1225

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: _____ WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/23/2006 5:00 PM KCC Agent: DONALD HOBEBRECHT

Actual Plugging Report:

Sanded back 50' above perforations with 4 sacks of cement on top of sand. Shot and pulled casing to 850' and spotted 35 sacks of cement. Pulled to 380' and circulated 150 sacks of cement to surface.

60/40 posmix with 4% gel

Copeland Acid & Cement

Perfs:

Top	Bot	Thru	Comments
4079	4085		
3740	3744		
3397	3401		

RECEIVED
KCC DISTRICT #2
APR 17 2006
WICHITA, KS

RECEIVED
APR 19 2006
KCC WICHITA

Remarks:

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)

INVOICED

DATE 4-19-06
SER. NO. 2006061500

Form CP-2/3

h

PT