

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-01147-00-00  
Spot: SWSWNW Sec/Twnshp/Rge: 24-30S-8W  
2893 feet from S Section Line, 5127 feet from E Section Line  
Lease Name: WEST SPIVEY UNIT Well #: 9  
County: KINGMAN Total Vertical Depth: 4377 feet

Operator License No.: 32446  
Op Name: MERIT ENERGY COMPANY  
Address: 13727 NOEL RD., STE 500  
DALLAS, TX 75240

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4377		200 SX CMT
SURF	8.625	195		250 SX CMT

\$1 142.25

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/06/2006 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Revd. from: JAY IVERSON Company: MERIT ENERGY COMPANY Phone: (620) 257-2719

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 03/06/2006 5:00 PM KCC Agent: DONALD HOBERECHT

**Actual Plugging Report:**

Sanded back to 4190' with 5 sacks of cement on top of sand. Shot casing at 1550'. Pulled to 1250' and spotted 35 sacks of cement. Pulled to 750' and spotted 35 sacks of cement. Pulled to 250' and circulated cement to surface with 80 sacks of cement.

60/40 posmix with 4% gel

Allied Cement #21260

**Perfs:**

Top	Bot	Thru	Comments
4272	4282		
4246	4254		
4240	4262		

RECEIVED  
KCC DISTRICT #2  
APR - 6 2006  
WICHITA, KS

RECEIVED  
APR 19 2006  
KCC WICHITA

Remarks:

Plugged through: CSG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

INVOICED

4-19-06

Form CP-2/3

2006061508

PICT