

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-21298-00-00  
Spot: NWSESE Sec/Twnshp/Rge: 18-30S-7W  
983 feet from S Section Line, 1064 feet from E Section Line  
Lease Name: JOHNSON EOG A Well #: 1  
County: KINGMAN Total Vertical Depth: 4590 feet

Operator License No.: 32446  
Op Name: MERIT ENERGY COMPANY  
Address: 13727 NOEL RD., STE 500  
DALLAS, TX 75240

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4589		200 SX
SURF	8.625	207		190 SX

\$ 149.18

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/02/2006 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: JAY IVERSON Company: MERIT ENERGY COMPANY Phone: (972) 628-1662

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 03/02/2006 5:00 PM KCC Agent: DONALD HOBERECHT

**Actual Plugging Report:**

Sanded back 50' above perforations with 4 sacks of cement on top of sand. Shot and pulled casing to 1250' and spotted 35 sacks of cement. Pulled to 750' and spotted with 35 sacks of cement. Pulled to 250' and circulated 90 sacks of cement to surface.

60/40 posmix with 4% gel

Allied #23348

**Perfs:**


Top	Bot	Thru	Comments
4296	4298		
4224	4226		
4207	4209		
4190	4192		
4180	4182		

RECEIVED  
KCC DISTRICT #2  
APR - 6 2006  
WICHITA, KS

RECEIVED  
APR 19 2006  
KCC WICHITA

Remarks:  
Plugged through: CSG

District: 02

Signed 

(TECHNICIAN)

INVOICED  
DATE 4-19-06  
NO. 2006061508



